



Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

Interdisciplinary Challenges of SRF Cryomodules

J. Holzbauer, Ph.D.

FRIB-APES Seminar

November 18th, 2022

Outline

- What IS an SRF Cryomodule, and why is it so complicated?
- How does this complexity impact final delivery and performance?
- Examples:
 - Stability of LCLS-II cryomodules (microphonics)
 - Transportation for LCLS-II (failures and successes) and planning for PIP-II
- Successful strategies for facing challenges (organizational, strategic, technical).
- Caveat: I'm focusing on Cryomodules, making a whole linac/accelerator is 10x more complicated. Also, I'm an RF guy; magnets are going to get short shrift, sorry.



What IS an SRF Cryomodule, and why is it so complicated?

High Energy Particles

- What does the science want?
 - More Energy!
 - Different science available
 - Controllable/Tunable Energy!
 - Dynamic behavior studies
 - Fine structure investigations like resonances
 - More Intensity!
 - Take data faster
 - Study rare processes
 - Rare isotopes
 - Neutrinos
 - Rare particle decays
 - Variety of Particle Beams!
 - The ability to create and use beams of any element/isotopes

- What do they REALLY want?


Wall power




Desired Beam

SRF Cryomodule (According to Wikipedia)


- The minimum criteria:
 - SRF Cavities (including coupler)
 - Cryogenic Vessel, insulation, fill and pumping
 - Beampipe
- Even in the broadest sense, what is needed to make build a particle accelerator? Electric and Magnetic fields.
- Many young scientists are trained this way (I do it myself), start from the RF cavity outward:
 - Maxwell leads to Helmholtz
 - Boundary conditions lead from waveguide to resonant structures
 - Coupled modes, tuning, bead pulls, coupling
 - Thermal breakdown, surface properties, material treatment, high pressure rinsing, etching, baking, doping
- All important, but not the whole picture



<https://en.wikipedia.org/wiki/Cryomodule>




SSR1 Cryomodule (PIP-II)



HB650 Cryomodule Cross-Section (PIP-II)

High power RF couplers are a great example of the real complexity:

- 300K to 2K transition
- Clean Vacuum to Air
- High power RF (kW to MW)
- Thin-walled bellows and copper plating
- Ceramic Windows
- Thermal intercepts, static/dynamic heat loads
- Significant alignment, contraction, movement requirements
- Challenging assembly



What is an SRF Cryomodule?


- A device that allows SRF cavities and superconducting magnets to accelerate/guide particle beams
- Why is it complicated:
 - Massive thermal challenges (minimize static heat leak, effectively manage dynamic heat load)
 - Ignoring complexity of Cryoplant and CDS!
 - Must preserve clean vacuum
 - Mechanical complexities (thermal contraction, alignment preservation, stability)
 - Enormously complex assembly process
 - Must integrate safety: pressure vessels, vacuum vessels, cryogenic circuit relieving, rigging and handling, transportation
 - Detailed instrumentation installation, wiring, and feedthroughs



How does this complexity impact delivery/performance?

Unintended Consequences: Vibration and Stability

- SRF cavities are well modeled as coupled harmonic oscillators with extremely high quality factors/low damping coefficients
- Remember: Acceleration of particles requires tight timing synchronization of all components and amplitude regulation
- Thus, cavities are driven at design frequency and must be forced, with complex RF control systems, to stay at phase and amplitude required for acceleration
- RF power is limited (and expensive!)
- **Why would a cavity change frequency?**



If the cavity shifts frequency from design (blue arrow), the response drops (green arrow). The cavity must be driven harder to maintain field at the cost of RF power.

LCLS-II Cavity Microphonics

- Cavity frequency is proportional to length (in this case)
- Optimization for LCLS-II gives enough RF power to control only ~13 Hz of detuning of the cavity
- $\frac{\Delta f}{f} \approx \frac{\Delta L}{L} ; \frac{13 \text{ Hz}}{1.3E9 \text{ Hz}} \cdot 1m \approx 10 \text{ nm}$
- At this level, many effects are very significant (*pressure*, temperature, dielectric constant, *resonant excitation*)
- Slow pressure control is generally quite good, *but fast pressure waves and mechanical vibration can have significant effects on cavity resonance*



Bare LCLS-II 1.3 GHz cavity after baking (lower), model of LCLS-II cavity end-level tuner (above)

LCLS-II pCM Testing at FNAL (~2017)



LCLS-II pCM Microphonics


Capturing microphonics of all 8 cavities in SEL

Many acceptance criteria can be satisfied in this condition (gradient, Q0, coupler, heat loads), BUT:

This cryomodule 'as is' would be *non-functional* in the machine.

Working group formed, about a dozen people, all stakeholders included in a strongly collaborative effort.

-RF, Cryo, Mech, Vacuum, Controls, LLRF, HPRF, Instrumentation, etc.




Many Avenues of Attack

- Cryogenic Concerns
 - Liquid quality/High gas velocities
 - **Thermo-Acoustic Oscillations/Valve Icing**
 - Weiring (liquid drag)
- Mechanical Concerns
 - Ground motion studies showed no sizable external vibrations.
 - Impulse testing could not be correlated with detuning
 - Why is cavity 1 worse?
- *TAOs are generally important for the tremendous heat leaks they can represent, not microphonics.*






Dynamic Frequency Behavior

- Vibration lines shift rapidly frequency and amplitude
 - Not mechanical resonances
 - Narrow-band cryogenic source(s) exciting wide-band, low frequency mechanical response




Low Pressure Tests

- Breakthrough occurred during a liquid level test (supplying via bypass valve), several minutes of 'quiet' were seen.
- Ben Hanson of AD-Cryo correlated this quiet with the transition to sub-critical supply pressure.
- Sub-critical via bypass and JT valves:
 - Vibration levels remained at low levels over a period of several hours
 - Ice on the head of the supply valve melted (both JT and bypass)
 - Helium consumption levels were lower than during comparable tests at super-critical injection pressures
- All three factors point to thermal-acoustic oscillations excited by the high pressure helium at the JT valve inlet



Critically Transition

Bypass Low Pressure Test - Cavity 1



Brief Introduction to TAOs

- Thermoacoustic oscillations generally occur in long gas-filled tubes with a large temperature gradient.
- Acoustic modes couple to mass transport up and down column especially well when gas density is strongly tied to temperature.
 - E.g. Warm gas from the top of a valve column moving to the cold bottom contracts, reducing pressure at warm region, driving the now cold gas back.
- Long valves and very low speed of sound in cold helium can easily give lowest acoustic modes at dangerous frequencies.
 - The quarter-wave mode in a 1 meter valve filled with 5K helium has a resonant frequency of $130 \text{ [m/s]} / 4 \text{ [m]} = 32 \text{ [Hz]}$.
- *These oscillations are generally important for the tremendous heat leaks they can represent, not microphonics.*

Cryogenic Valve Plumbing – Improved Valve Stems



- TAOs are a pressure/temperature oscillation in cryogenic lines (in this case, valve stems)
 - During testing, wipers were added to close space in valve stem, acting as a damping term for the TAOs
 - Significant improvement in heat load and microphonics levels and stability
 - Optimized valve stems with wipers were used on all cryomodules
 - 4-5 wipers, positioned to keep temperature ratio <4 as recommended by literature
 - Radiation hard material (PEEK)



Optimized wiper placement going forward



Cryogenic Valve Plumbing – Reverse Flow Path

- Test results show valve reversal (lower press in stem) significantly reduces/eliminate TAOs there
 - F1.3-01 configuration has valve stem at supply pressure (~3 bar)
 - Reversing flow will lower this pressure to sub-atmospheric, requiring guard gas to prevent contamination
 - All cryomodules will have guard gas, reversed valves
- Additional effort to mitigate TAOs in cryogenic distribution system should improve inlet temperature at test stand
- Reversed additional valve on the FNAL test stand (bypass) after latest test




Cavity 1 Mechanical Connections – Mitigation Beamline Gate Valve Bellows

- Replacing spool piece between cavity 1 and gate valve with a bellows is non-trivial
- Corrective fix includes extending tuner arms with fixture to connect to gate valve
 - When replacing spool piece with bellows, fixture fully supports gate valve
 - Current supports are long arms connected to the 300 mm pipe with needle bearing for the longitudinal motion
- With gate valve is supported by frame/helium vessel, the spool piece can be replaced with a bellows to separate mass from cavity/tuner system
- Two cryomodules with bellows have been tested at FNAL (F1.3-06/07)





Mitigation Steps in Cryomodule Design – 2 Phase Injection

- Liquid level control was coupled to input flow rate and the amount of flash gas generated across JT valve
 - Helium injection line impinged on liquid surface
 - Flash gas from JT caused liquid dragging
 - CM2 has baffles to protect liquid surface
 - CM3 has tangential injection into cap to reduce velocity and allow phase separation in addition to baffles
 - Should greatly reduce liquid dragging and improve liquid level stability, especially at high flow rates
 - Fluid simulation gives good confidence in improved injection behavior




CM2



CM3

Mitigation Diagnostic Tools

- Significant testing effort was spent on microphonics mitigation
- This effort built up a sizable infrastructure of testing tools and techniques
 - LLRF data capture system allows capture of simultaneous detuning on all cavities for long times
 - Scripting has been built out significantly to process and analyze this data, and expertise has been spread to multiple people
 - Can be correlated many sources of data via ACNET:
 - Impact/Vibration Measurements
 - Temperatures, Pressures, etc. from instrumentation
 - On-site, expert cryogenics support and flexibility are powerful diagnostic tools, allows testing in different cryogenics configurations
 - Leveraged significant work done at both labs on vibrational design and testing as a baseline




Unintended Consequences: Superfluid Acoustics


For active compensation purposes, we took many piezo to detuning transfer function

Mysterious 45-55 Hz lines on all cavities resisted explanation

- Dependent on cavity position
- Very high Q, hard to measure exactly, and seemingly variable in frequency
- 90 degrees out from piezo
- Varies with liquid level
- Severely suppressed at 4K



Helmholtz Resonance of 1.3 GHz Cavities




High JT Flow Rates and LCLS-II Module Tilt (0.5%)

High JT flow rates (high JT inlet temperature leads to lots of flash gas) gives large flow velocities (up to 70% of the speed of sound!).

JT injection hits directly on liquid surface (changed already in CM2).


The flash gas must escape to chimney, and this will push liquid downstream.

Remember that the upstream side is higher than the downstream side.



Bringing it all together

- Directly demonstrated correlation between:
 - Strong microphonics line amplitude and frequency
 - Liquid level
 - Cavity position
 - Resonance quality factor
- Done at Test Stand and in LCLS-II tunnel during commissioning
- Explained high piezo gain feedback microphonics during LCLS-II turn-on




Cavity 1 has lowest liquid level, thus highest Helmholtz Q, strongest microphonics impact

Unintended Consequences: One-off Activities

- LCLS-II Transportation, or, how the lab director finally learned my name (not a great thing)
- LCLS-II needed to ship dozens of modules from JLab and FNAL to SLAC
 - [LCLS-II Transport from FNAL on YouTube](#)

LCLS-II 1.3 CM Transport System




First Module at SLAC had Vented Clean String

- Hardware at bottom of vessel
 - Systematically revisited and improved all fasteners: Loctite, lock washers, Bellville washers, torque specifications, etc.
- Beam Position Monitor Flange missing hardware
 - Wrong grade of titanium Bolts stretched at required torque
- Several RF Coupler bellows totally fatigued and torn
 - Much bigger issue
- Transport Frame was totally mis-designed
 - Far too stiff, no isolation, no validation of performance
- Transport instrumentation wildly inadequate
 - Needed to develop systems for high quality data capture including CW 3D acceleration, pressure, temperature, GPS, including active remote monitoring


LCLS-II-4.5-ES-0403, Cold Button Beam Position Monitor

SLAC



CAD model cross section at RF power coupler


Center part of coupler between bellows is free to oscillate front to back in this image, cryomodule axis direction. Relative motion of cavity string and coupler in X (cavity string swinging side-to-side in this image) is also taken mostly via the inner coupler bellows.



Coupler internal motion during shipping


Analysis predicts 16 Hz. During last road test, we measured 15 Hz with amplitudes sufficient to damage the bellows.

F05 Cavity 4 Coupler
Shroud appears to ring
at 15 Hz





MODE 3 (16 Hz): Coupler Motion in Y Dir

F05 Example




“M-mount” constraint of assembled coupler



Neoprene constraint sits on G-10 block, held with tie-wrap.
Limits Z (coupler lateral) motion
but permits axial movement.

Bellows prediction, data, and specification

Note about the blue line specification:
 Below 2 mm peak to peak lateral offset, bellows stress is below the fatigue limit for 316L stainless.
 We selected a specification which sets the number of cycles at 2 mm peak to peak at no more than 100,000, two orders of magnitude below failure. We set the magnitude of high frequency cycles at 1 mm peak to peak, a factor of two below failure amplitude.




Expansion Joint Manufacturers' Association (EJMA) failure prediction

Data, measured cycles to failure:	RI-Th-1	39,986	●
	RI-Th-2	54,139	▲
	RI-Th-3	1,110,983	■
	RI-Th-4	11,182	★
	(Cold stroked 6 mm) CPI-Ameriflex-4	75,000	
	(Not cold stroked) CPI-Ameriflex-5	57,671	
	(Not cold stroked) CPI-Ameriflex-6	79,128	■
	(Cold stroked 9/-18/9 mm) CPI-Ameriflex-2	20,000	■
	(Cold stroked 9/-18/9 mm) CPI-Ameriflex-8	15,249	■
Specification:	40 Hz x 70 hours = 10 M cycles, 1 mm p-p		●
	and for 2 mm peak to peak, 100,000 cycles		●


Key improvements in transportation system

Improved shipping frame spring configuration 8 Springs



Reconfigured CM isolation frame springs:
lowered frame Z motion resonance from **13 Hz** to 7 Hz

Constrained bellows motion:
increased coupler Z motion resonance
from **15 Hz** to > 30 Hz



PIP-II Cryomodule Transport

The PIP-II Project is receiving over a dozen cryomodules from European partners as in-kind contributions

Overseas transport is identified as a high risk for the project, so significant resources are being spent to prepare



Dummy Load Testing at STFC-UKRI



Departure from STFC-UKRI



Return of Load to FNAL (Logistics matter!)



FESHM 10210 – Equipment Transport

- Transport failures for LCLS-II led FNAL to evaluate how engineering was done at the lab
- Fundamentally, one-off activities like transport are still major design effort and sources of risk, but are not always treated as such
- FESHM 10210 is a new kind of engineering oversight at the lab, ensuring that realistic risk assessment and mitigation are done for all major transports

 Fermilab	ES&H Manual	FESHM 10210 April 2022
---	-------------	---------------------------

FESHM 10210: EQUIPMENT TRANSPORT

Revision History

Author	Description of Change	Revision Date
Jeremiah Holzbauer	• Initial Release	April 28, 2022

 Fermilab	ESH&H Manual	FESHM 10210 April 2022
---	--------------	---------------------------

FESHM 10210: TECHNICAL APPENDIX

Revision History

Author	Description of Change	Revision Date
Jeremiah Holzbauer	Initial Release	April 28, 2022

Systematic Risk Assessments and Mitigations

Process Failure Modes and Effects Analysis (PFMEA)

Prepared: SBND Detector Transport
 Reviewed: Caru Team
 Core Team: Shikhi Shetty, Sai Kancharla, David Parkhi, Min Joon Kim, Steve Hentzschel, Nicolas M Conkey, L2 MBS: Monica Nunez, John Najdzian, Roberto Acciari, Anna Schokraft, Peter

PFMEA Date (Orig):
 Dec 8;
 Rev:

#	Process Step	Potential Failure Mode	Potential Effect(s) of Failure	Severity	Potential Cause(s) of Failure	Probab. Failure	Current Controls (Prevention)	Current Controls (Detection)	Detect. no.	Risk	Recommended Action(s)	Responsibility	Target Date	Actions Taken	Action Results			
															Sev.	Probab. Failure	Detect. no.	Risk
1	Assembly Transport Frame (stf) reconfiguration	in installation step is missed in the re-configuration of the stf	decrease of falling structural integrity; injury to personnel; damage to the detector	high	human error	unlikely	Assembly documentation in place; personnel has been instructed; lead technician (John) has previously led and completed this task in the practice for lead start in 2019; supervision through engineering team.	Inspection of re-configured stf by engineering to compare to transport	almost certain	Minor	continue with current prevention and detection controls	Shikhi Shetty	2 weeks prior to move date	-				
2	Moving out of DAB/Facility ND Building	Hillman rafter fail	stf in longer movable on tracks	low	material failure	rare	rafter fill repair; tested in 2019; mobile crane or building crane are in vicinity when moving on rafter	detector is not movable	almost certain	Negligible	have checks available; mobile crane or building crane are in vicinity when moving on rafter; stf have spare Hillman rafter	Shikhi Shetty	Complete	Assuming all recommended actions taken	low	rare	almost certain	Negligible
3	Moving out of DAB	stf gets stuck on the ramp on the way out of DAB	stf in longer movable on tracks	low	material failure	rare	steel plate, rafter guide; procedure developed from practice in 2019	detector is not movable	low	Negligible	see preventive measures	Shikhi Shetty	Complete	-				
4	Moving out of DAB	stf door not fit out the DAB door after ramp reurfacing	prevent transport	medium	design failure	rare	tested in 2019; ramp has been reurfaced since reurfacing	will have people on site to visually check the clearance during the transport	almost certain	Negligible	ensure the visual check is part of the work plan	Shikhi Shetty	2 weeks prior to move date	Assume work plan includes visual check	medium	rare	almost certain	Negligible
5	Moving out of DAB/Facility ND Building	Failure in curving ramp plate	stf is not curving ramp plate	medium	material failure	unlikely	inspect early; inspect prior to move day and on move day	visual	low	Minor	apply current controls	John Najdzian	3 days prior to move date	-				
6	Moving out of DAB/Facility ND Building	Mechanical failure of the tow line that makes the connection between the pulling of the truck and the stf	loss of control of detector; injury to personnel; damage to detector & equipment	high	material failure	rare	Fork truck load on back of the building; clear communication between operator in front and back will be covered (work plan)	visual of braking fork truck lift	low	Minor	see preventive measures	Shikhi Shetty	Complete	-				
7	Trailer loading/unloading	Rigging failure	Damage to stf & detector; personnel injury	high	Mobile crane or rigging equipment failure; operational error	unlikely	Professional crane lifting certificate and operator license; all workers briefed on work plan and HA	visual	low	Moderate	see preventive measures	Shikhi Shetty	On move day	-				
8	Trailer loading/unloading	Ground compression under mobile crane trailer	Damage to stf & detector; damage to lab infrastructure	high	unstable surface	rare	JULIE permits will be obtained; leveling added where needed	visual	almost certain	Negligible	see preventive measures	Shikhi Shetty	1 week prior to move date	-				
9	Trailer loading/unloading	Strepsen up during fastening/unfastening	Shock to the detector; possible damage to delicate component such as electronics, PMT	low	material failure	unlikely	Inspection of material; operation by trained personnel; work plan address fastening procedure	visual; QC check post move (1 month after)	low	Minor	see preventive measures	Shikhi Shetty	2 weeks prior to move date	-				
10	Transport	Movement of load on trailer	Shock to the detector; possible damage to delicate component such as electronics, PMT	low	material failure/improper securing of load	unlikely	Inspection of material; operation by trained personnel; work plan address fastening procedure; redundancy in securing chain & strap	visual; inspection if threshold indication is reached	moderate	Minor	see preventive measures	Shikhi Shetty	2 weeks prior to move date	-				
11	Transport	Light elements exposure of the detector	Damage to the light sensitive components of the detector; detector cleanliness compromised	medium	external element such as weather, branches, plastic, etc. in the plastic	possible	new layers of opaque plastic, and UV filtering plastic in place; route has been inspected several times and branches and new will be addressed prior to move date; move will not take place at certain weather conditions	visual inspection	low	Moderate	test that the plastic layers are secure in place; test all light sensors to monitor light exposure in real time during the transport	Monica Nunez & Nicolas M Conkey	2 weeks prior to move date	Assuming all recommended actions taken	medium	unlikely	moderate	Minor
12	Transport	Chains or fasteners for securing off the trailer break	Shock to the detector; possible damage to delicate component such as electronics, PMT; lead could shift on the truck	low	material failure/improper securing of load	possible	details of plan for securing the load in place; see work plan; experience from trial run with lead stf trailer; redundancy in securing chain & strap	visual inspection during the transport, as needed	low	Minor	Address redundancy in the chain & fastener strap when securing the load on the truck	Shikhi Shetty	2 weeks prior to move date	Will use 12 or require 46 pairs for lead securing	low	rare	low	Minor
13	Transport	Damage caused by collision with obstacle	Damage to the protective plastic layer (most likely); lead likely; damage to stf and/or trailer	medium	failure in securing load; operation by transport	rare	Prepare route ahead of move day; list of obstacles identified through trial run; transport speed (< 5 mph)	visual	almost certain	Negligible	ensure route preparation is complete by SBND team	Sai Kancharla & Shikhi Shetty	1 day prior to move date	Assuming all recommended actions taken	medium	rare	almost certain	Negligible
14	Transport	Loose shack during transport	Shock to the detector; possible damage to delicate component such as electronics, PMT	medium	Road condition	unlikely	Trial run; route to transport speed (< 5 mph); fix path/shack of move day; plate on uneven surface	visual; photo log data	low	Minor	ensure route preparation is complete by SBND team	Sai Kancharla & Shikhi Shetty	1 day prior to move date	Assuming all recommended actions taken	medium	rare	low	Minor
15	Transport	Truck/trailer or fork lift get a flat tire	Delay; need transport or move transport vehicle in challenging condition	low	material failure	unlikely	Trailer and truck under regular maintenance; tires will be inspected prior to move	visual	low	Minor	ensure inspection of truck & trailer including tires is complete	John Najdzian	morning of move day	Assuming all recommended actions taken	low	rare	low	Minor
16	Move into ND building	Hillman rafter fail to adjust for 90 degree rotation when moving in to the ND building	Delay; possible need for jacking up the stf for crane and repair; Note: this is after the detector is zeroed in the building; any remediation can be postponed to a later date	minimal	material failure	unlikely	The stf Hillman rafter have been specifically selected for this application and fulfill the requirements for this operation	stf will not move	low	Minor	none	Shikhi Shetty	complete	-				

Conclusions

- Accelerators are wildly interdisciplinary devices, one of the great uses of Applied Physics
 - My undergrad degree with UW-Madison was Applied Math, Engineering, and Physics
- Integrated performance requires close collaboration between disciplines, cross-training, and significant effort
- Design efforts should be widely communicative and broadly reviewed, and operations teams should be similarly broadly skilled and collaborative
- Intensive diagnostic development can pay strong dividends